

Date: Monday, 10/16/2006 2:01:20 PM  
 User: Kim Johnston

## Process Sheet

Customer : CU-DAR001 Dart Helicopters Services	Drawing Name : PLUG
Job Number : 29005	
Estimate Number : 10512	
P.O. Number : <i>N/A</i>	Part Number : D26511
This Issue : 10/16/2006 S.O. No. : <i>N/A</i>	Drawing Number : D2651 REV. B
Prsht Rev. : NC	Project Number : N/A
First Issue : <i>N/A</i> Type : MACHINED PARTS	Drawing Revision : B
Previous Run : 28691	Material : <i>N/A</i>
Written By : <i>[Signature]</i>	Due Date : 11/15/2006 Qty: 300 Um: Each
Checked & Approved By : <i>[Signature]</i>	
Comment : Est: A 02.04.15 New Issue NG	
Est: B 05.12.12 added deburr EC	

## Additional Product

Job Number:



Seq. #:	Machine Or Operation:	Description :
---------	-----------------------	---------------

1.0	M6061T6R0500	6061-T6 Round Bar .500"
-----	--------------	-------------------------



Comment: Qty.: 0.0421 f(s)/Unit Total : 12.6315 f(s) *13.0 f*

Material: 6061-T6 (QQ-A-225/8) 0.500" Dia  
 (M6061T6R0500)

Batch: *M102447*

*[Signature]* 06/10/30

2.0	HARDINGE	HARDINGE CNC LATHE SMALL
-----	----------	--------------------------



Comment: ~~HAAS CNC VERTICAL MACHINING #1~~ *Hardinge CNC Lathe Small*  
 1- Turn as per Folio FA219 and Dwg D2651

2- Deburr

*[Signature]* 06/10/30 300

3.0	QC2	INSPECT PARTS AS THEY COME OFF MACHINE
-----	-----	--



Comment: INSPECT PARTS AS THEY COME OFF MACHINE

*[Signature]* 06/10/30 300

4.0	QC8	SECOND CHECK
-----	-----	--------------



Comment: SECOND CHECK

*J.G* 06/10/31 300

5.0	SMALL FAB 1	SMALL & MEDIUM FAB RESOURCE 1
-----	-------------	-------------------------------



Comment: SMALL & MEDIUM FAB RESOURCE 1  
 Deburr ias per dwg D2651

*ml oc* 11/06 300

# Dart Aerospace Ltd

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector
06/12/11	2	permanent chg				U	06/12/11

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes ☒ No ☐ DQA: ☒ Date: 06/12/11  
 QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

NOTE: Date & initial all entries

Date: Monday, 10/16/2006 2:01:20 PM  
User: Kim Johnston

## Process Sheet

Customer: CU-DAR001 Dart Helicopters Services

Drawing Name: PLUG

Job Number: 29005

Part Number: D26511

Job Number:



Seq. #:

Machine Or Operation:

Description :

6.0

HAND FINISHING1

HAND FINISHING RESOURCE #1



counted

Comment: HAND FINISHING RESOURCE #1

Acid etch and Alodine as per QSI 005 4.1

yl 06/11/09 x ~~299~~ 300

7.0

POWDER COATING

POWDER COATING



Comment: POWDER COATING

Powder Coat White Gloss (Ref: 4.3.5.1) as per QSI 005 4.3

(Only larger section necessary)

yl 06/12/07 x 300

8.0

QC3

INSPECT POWDER COAT/CHEMICAL CONVERSION



Comment: INSPECT POWDER COAT

q m 06/12/08 (X300)

9.0

PACKAGING 1

PACKAGING RESOURCE #1



Comment: PACKAGING RESOURCE #1

Identify and Stock

Location: FP

q m 06/12/08 (300x)

10.0

QC21

FINAL INSPECTION/W/O RELEASE



Comment: FINAL INSPECTION/W/O RELEASE

06/12/11

Job Completion



u 06.12.11

**Dart Aerospace Ltd**

W/O:		WORK ORDER CHANGES					
DATE	STEP	PROCEDURE CHANGE	By	Date	Qty	Approval Chief Eng / Prod Mgr	Approval QC Inspector

Part No: \_\_\_\_\_ PAR #: \_\_\_\_\_ Fault Category: \_\_\_\_\_ NCR: Yes No DQA: \_\_\_\_\_ Date: \_\_\_\_\_

QA: N/C Closed: \_\_\_\_\_ Date: \_\_\_\_\_

NCR:		WORK ORDER NON-CONFORMANCE (NCR)						
DATE	STEP	Description of NC Section A	Corrective Action Section B			Verification Section C	Approval Chief Eng	Approval QC Inspector
			Initial Chief Eng	Action Description Chief Eng	Sign & Date			

**NOTE:** Date & initial all entries






DESIGN	DRAWN BY	DART AEROSPACE LTD HAWKESBURY, ONTARIO, CANADA	
CHECKED	APPROVED	DRAWING NO. D2651	REV. B SHEET 1 OF 1
DATE 03.12.19	TITLE PLUG		SCALE 1:1
A	97.03.25	NEW ISSUE	
B	03.12.19	ADD POWDER COAT, MS28775-008	


RELEASED

03.12.19

### D2651-1 PLUG:



### GROOVE DETAIL (SCALE 5:1)



SHOP COPY  
RETURN TO  
ENGINEERING  
UNCONTROLLED COPY  
SUBJECT TO AMENDMENT  
WITHOUT NOTICE  
WORK ORDER  
NO. 29005

### D2651-1 PLUG

- 1) MATERIAL: 6061-T6 (QQ-A-225/8) OR 1100-O (QQ-A-225/1)
- 2) FINISH: ACID ETCH & ALODINE PER DART QSI 005 4.1  
POWDER COAT WHITE (4.3.5.1) PER DART QSI 005 4.3
- 3) TOLERANCES ARE PER DART QSI 018 UNLESS OTHERWISE NOTED
- 4) ALL DIMENSIONS ARE IN INCHES
- 5) BREAK ALL SHARP EDGES 0.010 MAX

### D2651-3 O-RING

- 1) MATERIAL: BUNA N, 70 DUROMETER  
3/16 ID, 5/16 OD, 1/16 WIDTH  
(PARKER 2-008, MS28775-008 OR EQUIVALENT)

Copyright © 1997 by DART AEROSPACE LTD

THIS DOCUMENT IS PRIVATE AND CONFIDENTIAL AND IS SUPPLIED ON THE EXPRESS CONDITION THAT IT IS NOT TO BE USED FOR ANY PURPOSE OR COPIED OR COMMUNICATED TO ANY OTHER PERSON WITHOUT WRITTEN PERMISSION FROM DART AEROSPACE LTD.